

MRC-AD/MIS/2026/022

## Request for Quotation

<b>Type of Contract</b>	Company (Supply of Materials)
<b>Duration</b>	2 weeks from date of confirmation

## Background

The Maldivian Red Crescent (MRC) is an independent, voluntary, humanitarian organization established through the Maldivian Red Crescent Law (Law 7/2009). MRC's primary objective is to provide humanitarian aid and prevent and alleviate human suffering. It is the 187th member of the world's largest humanitarian movement — the International Red Cross and Red Crescent Movement — which every year helps millions of people whose lives have been devastated by crises or conflict. The Maldivian Red Crescent aims to be the nation's leading humanitarian organization, with Units spanned all over Maldives.

## Scope of Assignment

The selected company will be required to provide the following details based on the **attached Bill of Materials (BOM)**:

1. Unit rates and total cost for each item listed in the BOM
2. Delivery cost to GA. Villingili
3. Availability of materials
4. Estimated delivery timeline
5. Validity period of the quotation

Please note: This RFQ is for material **supply only with delivery**.

## Reporting Line

The focal point for the service provider will be the finance department of MRC.

## Terms & Payments

The service provider is to provide a quotation based on the items outlined listed in the attached Bill of Materials. A purchase order will be raised once confirmed and an invoice is to be raised upon completion of delivery. Invoice will be paid within 7 working days once the items are delivered.

## Submission Requirements

All interested should email their expression of interest to [vacancies@redcrescent.org.mv](mailto:vacancies@redcrescent.org.mv) before 14:00 on 5<sup>th</sup> February 2026, along with the Quotation.

Item No	Description	Unit	Qty	Material Rate	Labour	Amount
	<b>Typical Boundary wall 3Ft high</b>					
	<b>Boundary Length</b>	L Mtr	57.30			
	<b>Masonry wall</b>	L Mtr	53.30	4 mtr reduce for garage and main entrance		
1	<b>Foundation Lean</b>	m3	1.87			
	Cement	bag	9			
	M. Sand	bag	19			
	Aggregate	bag	33			
2	<b>Foundation Beam</b>	m3	2.29			
	Cement	bag	19			
	M. Sand	bag	39			
	Aggregate	bag	58			
	Glenium	Lit	3			
	T10	Nos	42			
	R6 ( aprox 230rings)	Nos	17.78			
	Plywood 12mm thk film faced	Nos	10.00			
	Timber 1.5"x2"x12'	Nos	20.00			
	Wooden screw 1.5" flat head black	Nos	200.00			
	Wooden screw 4" hex head	Nos	50.00			
3	<b>Columns</b>	m3	0.72			
	Cement	bag	6			
	M. Sand	bag	12			
	Aggregate	bag	18			
	Glenium	Lit	0.11			
	T10	Nos	12.41			
	R6	Nos	10.34			
	Plywood 12mm thk film faced	Nos	8.00			
	Timber 1.5"x2"x12'	Nos	20.00			
	Wooden screw 1.5" flat head black	Nos	200.00			
	Wooden screw 4" hex head	Nos	50.00			
	Gunny bags	Nos	40.00			
4	<b>Top Beam</b>	m3	1.60			
	Cement	bag	14			
	M. Sand	bag	27			
	Aggregate	bag	41			
	Glenium	Lit	2.00			
	T10	Nos	20			
	R6	Nos	14			
	Plywood 12mm thk film faced	Nos	20.00			
	Timber 1.5"x2"x12'	Nos	20.00			
	Wooden screw 1.5" flat head black	Nos	200.00			
	Wooden screw 4" hex head	Nos	50.00			
5	<b>Masonry Works</b>	m2	51.57			
	Masonry block 6" X 6" X 12"	nos	1,146.00			
	Cement	bag	7			
	M. Sand	bag	41			
6	<b>Plastering Works 25mm thick</b>	m2	113.45			
	Cement	bag	30			
	M. Sand fine	bag	132			
7	<b>Paint Finishes</b>	m2	113.45			
	Wall Sealer	Lit	19.00			
	Paint	Lit	28.00			